


All internal stud work to be 47 x 100 C24 timber @ 400cc, lined to room sides with 12 WBP ply and 15 gypsum based plasterboard, 3 nominal skim finish, fully insulated with Knauf Acoustic partition roll. Gyproc Soundbloc to studs between wetrooms, bedrooms and living spaces.

PROPOSED FIRST FLOOR PLAN (MAIN RANGE) 1:50@ A 1







Proposed First Floor Plan Main Range Magpie Farm Michael Holland & Denise O'Donoghue 1:50 @ A1

checked <u>CF</u>

status CONSTRUCTION 08/10/2024 399-C-252

KEY

Padstones Stone - type TBC

Element to be demolished Joinery detail (Floor-J-#)