

**Iain St John,  
Unit 24,  
Cromwell Business Park,  
Chipping Norton,  
OX7 5SR**

**Alarm & CCTV**

**13/03/24**

wurzel 

## Overview Of Installation

### CCTV

**Wurzel Recommend to install the following:**

#### **CCTV:**

- New NVR for the existing CCTV. (We do not know who has access to the current/existing NVR and it is locked).
- New CCTV as Wurzel cannot access the CCTV. (We do not know who has access to the current/existing CCTV and it is/may be locked).
- Raise the existing CCTV so that they are out of reach.
- Run a new cable from the router to the NVR.
- Install a KVM cable from the NVR to the new office upstairs for the display monitor.

#### **Benefits of replacing existing CCTV:**

- Guaranteed that we can support them
- Use of smart features (Intrusion Detection, Line Crossing, Etc)
- Designed to work with the NVR
- Swapping to Turret cameras makes it harder for them to be knocked - better design for the use case
- 3 Year Guarantee
- Use of deterrent features - flashing lights on cameras when people are detected makes them look at the camera. Audio alarms / 2 way audio can also be used. (Turrets Only).
- Can view the office CCTV from Cherwell farm.

## Overview Of Installation

### Alarm

**Wurzel to install the following:**

**Alarm:**

- 2X Door mag detectors.
- 4X PIR Detectors.
- New alarm panel.
- Relocate 1st floor pir to watch stairs instead of hallway.

**Benefits of using alarm monitoring / servicing:**

- Constant monitoring of the alarm - will also notify of any alarm faults (such as the alarm not connecting to the ARC) which prevents against external vulnerabilities - Such as the internet going down.
- Ensures that there is a key holder acknowledgement.
- Doesn't depend on the Pyronix Cloud service.
- Included yearly service of the alarm.
- Preferred by insurers - can bring premiums down.
- We would also encourage you to go for the alarm monitoring and maintenance package we offer too. £22.00 + VAT per month.

## Overview Of Installation

### Alarm

**Wurzel to install the following:**

#### **Wifi:**

- Install a new wifi point for the upstairs office.
- Cable the existing ground floor wifi point correctly and wall/ceiling mount it.
- New switch to power the wifi points and remove the injector currently installed.

## Existing CCTV Plan

→ = Existing CCTV



Existing NVR and Monitor  
located in a separate room

## New CCTV Plan

- = Upgrade to Bullet CCTV
- = Upgrade to Turret CCTV

Raise the existing outdoor CCTV so that they are out of reach.



Existing NVR and Monitor  
located in a separate room

## Existing Alarm Plan

→ = Existing PIR Sensor



Existing alarm panel to be replaced

## New Alarm Plan

→ = New PIR Sensor

Relocate 1st floor pir to  
watch stairs instead of hallway.



New alarm panel

## Wifi Point Plan



Mount the existing wifi point correctly onto the wall/ceiling.

Install a new wifi point for the upstairs office

**Site Surveyors**  
**Maaliq Okten**  
**Sam Savin**

The Old Coal Yard, Gagingwell, Enstone, Chipping  
Norton, OX7 4EF

**01865 655393**  
**07957 649774**

[Sales@wurzel.co.uk](mailto:Sales@wurzel.co.uk)

wurzel 